ALTA/NSPS LAND TITLE SURVEY

WEST HALF OF THE S.W. QUARTER, SECTION 33, TOWNSHIP 19 NORTH, RANGE 5 EAST
NOBLESVILLE TOWNSHIP, HAMILTON COUNTY, INDIANA

LAND DESCRIPTION

DESCRIPTION OF REAL ESTATE PER TITLE COMMITMENT, STEWART TITLE FILE No. 01077–19886, DATED OCT 17, 2017

A PART OF THE WEST HALF OF SECTION 33, TOWNSHIP 19 NORTH, RANGE 5 EAST, NOBLESVILLE TOWNSHIP, HAMILTON COUNTY, INDIANA, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A HARRISON MONUMENT AT THE SOUTHWEST CORNER OF THE EAST HALF OF THE SOUTHWEST QUARTER OF SECTION 33, TOWNSHIP 19 NORTH, RANGE 5 EAST, HAMILTON COUNTY, INDIANA; THENCE NORTH 89 DEGREES 36 MINUTES 57 SECONDS EAST (ASSUMED BEARING) ON THE SOUTH LINE OF SAID SOUTHWEST QUARTER 460.33 FEET TO A POINT ON THE NORTHWEST RIGHT–OF–WAY LINE OF STATE ROAD 32 AS PER RIGHT–OF–WAY PLANS FOR F.A. PROJECT NO. 251, F.Y. 1931; THENCE NORTH 75 DEGREES 45 MINUTES 58 SECONDS EAST ON SAID RIGHT–OF–WAY LINE 10.37 FEET TO A CORNER OF THE REAL ESTATE CONVEYED TO THE STATE OF INDIANA IN INSTRUMENT NO. 98–26927 IN THE OFFICE OF THE RECORDER OF HAMILTON COUNTY, INDIANA; THENCE THE FOLLOWING FOUR CALLS ON THE PERIMETER OF SAID REAL ESTATE; 1.) NORTH 14 DEGREES 14 MINUTES 02 SECONDS WEST 12.57 FEET; 2.) NORTH 75 DEGREES 45 MINUTES 58 SECONDS EAST 485.56 FEET; 3.) NORTH 63 DEGREES 37 MINUTES 56 SECONDS EAST 67.12 FEET; 4.) NORTH 75 DEGREES 45 MINUTES 58 SECONDS EAST 341.81 FEET TO A POINT IN THE EAST LINE OF SAID SOUTHWEST QUARTER; THENCE NORTH 00 DEGREES 16 MINUTES 43 SECONDS EAST ON THE EAST LINE OF SAID SOUTHWEST QUARTER 2409.92 FEET TO THE SOUTHEAST CORNER OF THE NORTHWEST QUARTER OF SAID SECTION; THENCE NORTH 00 DEGREES 14 MINUTES 10 SECONDS EAST ON THE EAST LINE OF SAID NORTHWEST QUARTER 1896.09 FEET TO A POINT ON THE SOUTH LINE OF THE REAL ESTATE DESCRIBED IN INSTRUMENT NO. 2004–54487; THENCE SOUTH 89 DEGREES 27 MINUTES 45 SECONDS WEST ON SAID SOUTH LINE AND THE PROLONGATION THEREOF 459.90 FEET TO A POINT ON THE EAST LINE OF THE REAL ESTATE DESCRIBED IN INSTRUMENT NO. 2005–79234; THENCE FOLLOWING TWO CALLS ON THE PERIMETER OF SAID REAL ESTATE: 1.) SOUTH 01 DEGREES 21 MINUTES 51 SECONDS WEST 0.51 FEET; 2.) SOUTH 89 DEGREES 29 MINUTES 51 SECONDS WEST 467.00 FEET TO A POINT ON THE WEST LINE OF THE REAL ESTATE DESCRIBED IN INSTRUMENT NO. 88–15012; THENCE NORTH 01 DEGREES 21 MINUTES 51 SECONDS EAST ON SAID WEST LINE 0.22 FEET TO A POINT ON THE SOUTH LINE OF DEED BOOK 283, PAGE 632; THENCE SOUTH 89 DEGREES 27 MINUTES 45 SECONDS WEST ON SAID SOUTH LINE AND THE PROLONGATION THEREOF 355.01 FEET TO A POINT ON THE WEST LINE OF THE EAST HALF OF SAID NORTHWEST QUARTER; THENCE SOUTH 00 DEGREES 25 MINUTES 51 SECONDS WEST ON SAID WEST LINE 1894. 16 FEET TO THE SOUTHWEST CORNER OF SAID EAST HALF; THENCE SOUTH 00 DEGREES 16 MINUTES 38 SECONDS WEST IN THE WEST LINE OF THE EAST HALF OF SAID SOUTHWEST QUARTER 2650.55 FEET TO THE POINT OF BEGINNING, CONTAINING 135.97 ACRES, MORE OR LESS.

EXCEPT THEREFROM:
PART OF THE EAST ONE–HALF (1/2) OF THE WEST ONE–HALF (1/2) OF SECTION 33, TOWNSHIP 19 NORTH, RANGE 5 EAST, HAMILTON COUNTY, INDIANA, AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT THE NORTHWEST CORNER OF THE EAST HALF OF THE NORTHWEST QUARTER OF SECTION 33, TOWNSHIP 19 NORTH, RANGE 5 EAST, HAMILTON COUNTY, INDIANA; THENCE SOUTH 00 DEGREES 25 MINUTES 51 SECONDS WEST ALONG THE WEST LINE OF THE EAST HALF OF THE NORTHWEST QUARTER OF SECTION 33, TOWNSHIP 19 NORTH, RANGE 5 EAST, A DISTANCE OF 760 FEET TO THE SOUTHWEST CORNER OF PROPERTY CONVEYED TO EARL AND NORMA HORSMAN BY INSTRUMENT NUMBER 98–38664, OF THE HAMILTON COUNTY RECORDER AND THE POINT OF BEGINNINGOF THE HEREIN DESCRIBED TRACT; THENCE NORTH 89 DEGREES 27 MINUTES 45 SECONDS EAST A DISTANCE OF 352 FEET TO A POINT; THENCE SOUTH 00 DEGREES 25 MINUTES 51 SECONDS WEST A DISTANCE OF 382 FEET TO A POINT; THENCE SOUTH 89 DEGREES 27 MINUTES 45 SECONDS WEST A DISTANCE OF 352 FEET TO SAID WEST LINE OF THE EAST HALF OF THE NORTHWEST QUARTER OF SECTION 33, TOWNSHIP 19 NORTH, RANGE 5 EAST; THENCE NORTH 00 DEGREES 25 MINUTES 51 SECONDS EAST A DISTANCE OF 382 FEET TO THE POINT OF BEGINNING SAID TRACT CONTAINING APPROXIMATELY 3.086 ACRES, MORE OR LESS.

ALSO EXCEPT THEREFROM:
A PART OF THE WEST HALF OF SECTION 33, TOWNSHIP 19 NORTH, RANGE 5 EAST, HAMILTON COUNTY, INDIANA, AND BEING THAT PART OF THE GRANTOR'S LAND LYING WITHIN THE RIGHT OF WAY LINES DEPICTED ON THE ATTACHED RIGHT OF WAY PARCEL PLAT, MARKED EXHIBIT "B", DESCRIBED AS FOLLOWS: BEGINNING AT THE SOUTHWEST CORNER OF THE EAST HALF OF THE SOUTHWEST QUARTER OF SAID SECTION 33 DESIGNATED AS POINT "133" ON SAID PLAT; THENCE NORTH 0 DEGREES 16 MINUTES 33 SECONDS EAST 200.42 FEET ALONG THE EAST LINE OF SAID HALF–QUARTER SECTION; THENCE SOUTH 89 DEGREES 43 MINUTES 27 SECONDS EAST 16.50 FEET TO THE EAST BOUNDARY OF PROMISE ROAD DESIGNATED AS POINT "409" ON SAID PLAT; THENCE CONTINUING SOUTH 89 DEGREES 43 MINUTES 27 SECONDS EAST 23.50 FEET TO POINT "408" DESIGNATED ON SAID PLAT; THENCE 0 DEGREES 16 MINUTES 33 SECONDS WEST 80.00 FEET TO POINT "407" DESIGNATED ON SAID PLAT; THENCE SOUTH 15 DEGREES 40 MINUTES 10 SECONDS EAST 72.80 FEET TO POINT "406" DESIGNATED ON SAID PLAT; THENCE SOUTH 46 DEGREES 17 MINUTES 50 SECONDS EAST 71.47 FEET TO THE SOUTH LINE OF SAID HALF–QUARTER SECTION DESIGNATED AS POINT "405" ON SAID PLAT; THENCE SOUTH 89 DEGREES 36 MINUTSE 58 SECONDS WEST 95.41 FEET ALONG SAID SOUTH LINE TO THE EAST BOUNDARY OF SAID PROMISE ROAD; THENCE CONTINUING SOUTH 89 DEGREES 36 MINUTES 58 SECONDS WEST 16.50 FEET ALONG SAID SOUTH LINE TO THE POINT OF BEGINNING AND CONTAINING 0.252 ACRES, MORE OR LESS, INCLUSIVE OF THE PRESENTLY EXISTING RIGHT OF WAY WHICH CONTAINS 0.076 ACRES, MORE OR LESS.

ALSO EXCEPT THEREFROM:
A PART OF THE WEST HALF OF SECTION 33, TOWNSHIP 19 NORTH, RANGE 5 EAST, HAMILTON COUNTY, INDIANA, AND BEING THAT PART OF THE GRANTOR'S LAND LYING WITHIN THE RIGHT OF WAY LINES DEPICTED ON THE ATTACHED RIGHT OF WAY PARCEL PLAT, MARKED EXHIBIT "B", DESCRIBED AS FOLLOWS: COMMENCING THE SOUTHWEST CORNER OF THE EAST HALF OF THE SOUTHWEST QUARTER OF SAID SECTION 33 DESIGNATED AS POINT "133" ON SAID PLAT; THENCE NORTH 89 DEGREES 36 MINUTE 58 SECONDS EAST 16.50 FEET ALONG THE SOUTH LINE OF HALF–QUARTER SECTION TO THE EAST BOUNDARY OF PROMISE ROAD; THENCE CONTINUING NORTH 89 DEGREES 36 MINUTES 58 SECONDS EAST 95.41 FEET ALONG SAID SOUTH LINE TO POINT "405" DESIGNATED ON SAID PLAT; THENCE CONTINUING NORTH 89 DEGREES 36 MINUTES 58 SECONDS EAST 91.63 FEET ALONG SAID SOUTH LINE TO THE POINT OF BEGINNING OF THIS DESCRIPTION DESIGNATED AS POINT "404" ON SAID PLAT; THENCE NORTH 76 DEGREES 57 MINUTES 56 SECONDS EAST 546.15 FEET TO POINT "403" DESIGNATED ON SAID PLAT; THENCE SOUTH 14 DEGREES 14 MINUTES 05 SECONDS EAST 37.45 FEET TO THE NORTHERN BOUNDARY OF S.R. 32 DESIGNATED AS POINT "402" ON SAID PLAT; THENCE SOUTH 75 DEGREES 45 MINUTES 59 SECONDS WEST 286.42 FEET ALONG SAID NORTHERN BOUNDARY; THENCE SOUTH 14 DEGREES 14 MINUTES 01 SECOND EAST 12.56 FEET ALONG SAID BOUNDARY; THENCE SOUTH 75 DEGREES 45 MINUTES 55 SECONDS WEST 10.42 FEET ALONG SAID BOUNDARY TO THE SOUTH LINE OF SAID HALF–QUARTER SECTION; THENCE SOUTH 89 DEGREES 36 MINUTES 58 SECONDS WEST 256.65 FEET ALONG SAID SOUTH LINE TO THE POINT OF BEGINNING AND CONTAINING 0.440 ACRES, MORE OR LESS.

VICINITY MAP
NOT TO SCALE



POINT #	REMARKS
130 131 132 133 134 135	FOUND REBAR
129 138 139	5/8" IRON ROD WITH YELLOW CAP STAMPED "MILLER S0083" SET
120 121 122 123	CONCRETE R/W MARKER FOUND
124 125 126 127 128	
119	NO POINT SET OR FOUND

FLOOD ZONE DEFINITION

ZONE	EXPLANATION
"X"	AREAS DETERMINED TO BE OUTSIDE 500–YEAR FLOODPLAIN.

THE SUBJECT PROPERTY IS NOT LOCATED IN A SPECIAL FLOOD HAZARD AREA AS ESTABLISHED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY NATIONAL FLOOD INSURANCE PROGRAM AS PER SCALED INTERPRETATION OF FLOOD RATE MAP #18057C0161 G. AREA IN ZONE "X" MAP DATED 11–19–2014.

BENCHMARK INFORMATION

HORIZONTAL AND VERTICAL CONTROL:

COORDINATE SYSTEM:
US STATE PLANE 1983 (AT GROUND)

PROJECT DATUM:
WORLD GEODETIC SYSTEM (WGS 1984)

VERTICAL DATUM
NAVD 88

ZONE:
INDIANA EAST 1301

GEOID MODEL:
GEOID12A (CONUS)

COORDINATE UNITS US SURVEY FEET
DISTANCE UNITS US SURVEY FEET
HEIGHT UNITS US SURVEY FEET

SURVEYOR'S REPORT

IN ACCORDANCE WITH TITLE 865, ARTICLE 1, CHAPTER 12 OF THE INDIANA ADMINISTRATIVE CODE (RULES FOR LAND SURVEYS IN INDIANA), THE FOLLOWING OBSERVATIONS AND OPINIONS ARE SUBMITTED REGARDING THE VARIOUS UNCERTAINTIES IN THE LOCATIONS OF THE LINES AND CORNERS ESTABLISHED THIS SURVEY AS A RESULT OF UNCERTAINTIES IN REFERENCE MONUMENTATION; IN RECORD DESCRIPTIONS AND PLATS; IN LINES OF OCCUPATION; AND AS INTRODUCED BY RANDOM ERRORS IN MEASUREMENT ("RELATIVE POSITIONAL ACCURACY"). THERE MAY BE UNWRITTEN RIGHTS ASSOCIATED WITH THESE UNCERTAINTIES. THE CLIENT SHOULD ASSUME THERE IS AN AMOUNT OF UNCERTAINTY ALONG ANY LINE EQUAL IN MAGNITUDE TO THE DISCREPANCY IN THE LOCATION OF THE LINES OF POSSESSION FROM THE SURVEYED LINES.

THERE MAY BE DIFFERENCES OF DEED DIMENSIONS VERSUS MEASURED DIMENSIONS ALONG THE BOUNDARY LINES SHOWN HEREON AND LIKEWISE, THERE MAY BE FOUND SURVEY MARKERS NEAR, BUT NOT PRECISELY AT, SOME BOUNDARY CORNERS. IN CASES WHERE THE MAGNITUDE OF THESE DIFFERENCES ARE LESS THAN THE RELATIVE POSITIONAL ACCURACY AND LESS THAN THE UNCERTAINTY IDENTIFIED FOR THE REFERENCE MONUMENTATION (DISCUSSED BELOW), THE DIFFERENCES MAY BE CONSIDERED INSIGNIFICANT AND ARE SHOWN ONLY FOR PURPOSES OF MATHEMATICAL CLOSURE. SUCH DIFFERENCES THAT ARE GREATER THAN THE RELATIVE POSITIONAL ACCURACY AND THE UNCERTAINTY IN REFERENCE MONUMENTATION SHOULD BE CONSIDERED WORTHY OF NOTICE AND ARE THEREFORE DISCUSSED FURTHER BELOW.

THIS SURVEY AND REPORT ARE BASED IN PART UPON OPINIONS FORMED IN ACCORDANCE WITH AN INDIANA LAND SURVEYOR'S RESPONSIBILITY TO CONDUCT A SURVEY IN ACCORDANCE WITH "LAW OR A PRECEDENT" (865 IAC 1–12–11(5), RULES OF THE INDIANA STATE BOARD OF REGISTRATION FOR LAND SURVEYORS). SINCE INDIANA HAS NO STATUTES ADDRESSING HOW TO RESOLVE BOUNDARY LINES, A SOLUTION BASED ON PRINCIPLES DERIVED FROM COMMON LAW PRECEDENT MUST BE RELIED UPON AS THE BASIS FOR A BOUNDARY RESOLUTION. UNLESS OTHERWISE NOTED OR DEPICTED HEREON, THERE IS NO EVIDENCE OF OCCUPATION ALONG THE PERIMETER LINES OF THE SUBJECT TRACT. ALL SURVEY MONUMENTS SET OR FOUND THIS SURVEY ARE FLUSH WITH EXISTING GRADE UNLESS OTHERWISE NOTED.

THE RELATIVE POSITIONAL ACCURACY (DUE TO RANDOM ERRORS IN MEASUREMENT) OF THE CORNERS OF THE SUBJECT TRACT ESTABLISHED THIS SURVEY DOES NOT EXCEED THAT ALLOWABLE FOR A RURAL CLASS SURVEY (0.26 FEET PLUS 200 PPM) AS DEFINED IN IAC 865.

THE WITHIN SURVEY IS AN ALTA/NSPS LAND TITLE SURVEY OF A TRACT OF REAL ESTATE DESCRIBED IN INSTRUMENT No. 2006074011WITH EXCEPTION OF THE RIGHT OF WAY OF STATE ROAD 32 PER INSTRUMENT No. 2009025993.

BASIS OF BEARING: ASSUMED BEARING

CONTROLLING MONUMENTS:

FOUND EXISTING SECTION CORNER MONUMENTS, PRIOR MILLLER SURVEYING, AND PRIOR CRIPE SURVEY AND PRIOR WEIHE ENGINEERING SURVEY.

IN MY OPINION, THERE IS 0.5 FEET OF UNCERTAINTY IN THE LOCATION OF THESE MONUMENTS.

1. POSSESSION TO THE SOUTH IS THE IMPROVEMENTS OF STATE ROAD No. 32. THE POSSESSION TO THE EAST IS TO THE IMPROVEMENTS OF PROMISE ROAD. NO EVIDENCE OF POSSESSION WAS FOUND TO THE WEST AND NORTH .

NO TITLE "GAPS" AND/OR "OVERLAPS" WERE FOUND WITH CURRENT DEED OF RECORDS

2. THE ACCURACY OF ANY FLOOD HAZARD DATA SHOWN ON THIS REPORT IS SUBJECT TO MAP SCALE UNCERTAINTY AND TO ANY OTHER UNCERTAINTY IN LOCATION OR ELEVATION ON THE REFERENCED FLOOD INSURANCE RATE MAP. THE WITHIN DESCRIBED TRACT OF LAND LIES WITHIN ZONE "X" AS SAID TRACT PLOTS BY SCALE ON COMMUNITY PANEL NUMBER 18057C0161 G OF THE FLOOD INSURANCE RATE MAPS FOR HAMILTON COUNTY, INDIANA (MAPS DATED 11–19–2014)

3. OWNERSHIP INFORMATION INDICATED HEREON IS AS IDENTIFIED IN COUNTY RECORDS ON 6–11–2018.

4. THE SURVEY HEREIN DOES NOT PURPORT TO SHOW THE WATERSHED AREAS AFFECTING THE SUBJECT PARCELS NOR DOES IT PURPORT TO SHOW THE PRESENCE OR ABSENCE OF ALL REGULATED OR NON–REGULATED DITCHES OR DRAINS.

TITLE COMMITMNET NOTES PER STEWART TITLE FILE No. 01077–19886, DATED OCTOBER 17, 2017

12. TERMS AND PROVISIONS OF UTILITY EASEMENT IN FAVOR OF INDIANA BELL TELEPHONE COMPANY, INCORPORATED, DATED OCTOBER 16, 1984 AND RECORDED NOVEMBER 30, 1984 IN BOOK 2, PAGE 227, INSTRUMENT NO. 8416188. (AS SHOWN ON THE DRAWING)

13. TERMS AND PROVISIONS OF UTILITY EASEMENT IN FAVOR OF INDIANA BELL TELEPHONE COMPANY, INCORPORATED, DATED APRIL 9, 1985 AND RECORDED APRIL 26, 1985 IN BOOK 2, PAGE 743, INSTRUMENT NO. 85-5247(AS SHOWN ON THE DRAWING)

14. TERMS, PROVISIONS AND NOTICE AS PROVIDED IN RESOLUTION 8-27-01-1 OF THE HAMILTON COUNTY DRAINAGE BOARD CONCERNING THE ELWOOD WILSON DRAIN DATED AUGUST 27, 2001 AND RECORDED AUGUST 27, 2001 AS INSTRUMENT NO. 200100053707.
(AS SHOWN ON THE DRAWING)

15. TERMS AND PROVISIONS OF GAS LINE EASEMENT IN FAVOR OF INDIANA GAS COMPANY, INC., DATED AUGUST 28, 1999 AND RECORDED OCTOBER 3, 2001 AS INSTRUMENT NO. 200100063165. (AS SHOWN ON THE DRAWING)

16. TERMS AND PROVISIONS OF UTILITY EASEMENT IN FAVOR OF INDIANA-AMERICAN WATER COMPANY, INC. DATED FEBRUARY 27, 2007 AND RECORDED MARCH 5, 2007 AS INSTRUMENT NO. 2007012678. (AS SHOWN ON THE DRAWING)

17. TERMS AND PROVISIONS OF UTILITY EASEMENT IN FAVOR OF INDIANA-AMERICAN WATER COMPANY, INC., DATED FEBRUARY 27, 2007 AND RECORDED MARCH 5, 2007 AS INSTRUMENT NO. 2007012679. (AS SHOWN ON THE DRAWING)

CERTIFICATION

TO STEWART TITLE
BOOMERANG DEVELOPMENT COMPANY, LLC
John GregorY Fisher, Trustee of Ruth L Fisher Revocable Trust

THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH THE 2016 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS, JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS, AND INCLUDES ITEMS 1, 2, 3, 4, 6, 7(a), 8, 9, 10, 11(a), and 13 OF TABLE A THEREOF. THE FIELDWORK WAS COMPLETED ON (7–17–18).

DATE OF PLAT OR MAP: 7–18–18

SIGNED: _____
K. NATHAN ALTHOUSE, PLS
REGISTRATION NO. LS20400007

UTILITY NOTE

THIS SURVEY REFLECTS ABOVE GROUND INDICATIONS OF EXISTING UTILITIES. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED, ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM THE INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES.

THIS SURVEY PLAT HAS BEEN PREPARED FOR USE ON THIS PARTICULAR PROJECT AND FOR THE EXCLUSIVE USE OF THE PERSON(S) OR ENTITY HEREON NAMED AND IS NOT CERTIFIED TO OR TO BE USED BY ANY OTHER PARTY. THE EVIDENCE, POSSESSION, OWNERSHIP, CONDITIONS ETC. COULD CHANGE CONSTANTLY AND THE USE OF THIS SURVEY IS LIMITED ONLY TO THE DATE INDICATED HEREIN.

THE LOCATION OF THE TITLE LINES AND CORNERS ARE SUBJECT TO THE EVIDENCE FOUND IN THE PERFORMANCE OF THIS SURVEY. ADDITIONAL EVIDENCE PRESENTED TO MILLER SURVEYING, INC. MAY ALTER THE LOCATION OF THE TITLE LINES AND CORNERS.

THIS SURVEY IS NOT COMPLETE AND/OR VALID WITHOUT BOTH PAGES.

GRAPHIC SCALE
0 100 200 400
SCALE : 1" = 200'

REVISIONS

REV. DATE	BY	DESCRIPTION

MILLER SURVEYING INC.
948 CONNER STREET
NOBLESVILLE INDIANA 46060
PH. # (317) 773–2644 FAX 773–2694

LOCATION: WEST HALF SOUTHWEST QUARTER 33–19–5 HAMILTON COUNTY IN	DRAWN BY: KNA	PREPARED BY: KNA
	SCALE: 1" = 100'	FIELD BOOK: DC
FIELD WORK COMPLETED: 7–16–18	DATE: 7–18–18	PAGE:
CLIENT: CORBY THOMPSON	JOB NUMBER	SURVEY 4 FILE:
DESCRIPTION: ALTA/NSPS LAND TITLE SURVEY	B37962	